



COUNTY OF DANE
DEPARTMENT OF ADMINISTRATION
PURCHASING DIVISION

City County Building
210 Martin Luther King Jr. Blvd. Room 425
Madison, WI 53703-3345

GREG BROCKMEYER
Director of Administration

CHARLES HICKLIN
Controller

Date: June 18, 2019
To: All Proposers
Subject: Addendum #1 to Bid# 119067 – HMA Pavement

This addendum contains revisions to Bid# 119067. All revisions are highlighted in **yellow with red font**.

TERMINATION DATE

Asphaltic paving on these projects shall be terminated before November 15, **2019**. Any work performed beyond that date will be only by permission of the County.

BID SPECIFICATIONS – INDIVIDUAL PROJECT DESCRIPTION AND SPECIFICATIONS

The following language is added to the Bid Specifications – Individual Project Description and Specifications section for both CTH P and CTH S:

Pulverized & re-laid pavement will be measured at 32 feet mainline plus widened pavement areas at intersections. Pulverized material is to be re-laid to a consistent width 2 foot wider than the finished pavement. Existing pavement depth from plans is approximately 8-inches. Split lift compaction will not be required on this project.

PRICE PROPOSAL SECTIONS

Please use the attached Price Proposal sections when submitting a bid. The revised price proposal sections correct the type of HMA Pavement.

Please acknowledge receipt of this addendum by checking the “Addendum #1” box in **Section 2 – Vendor Information** of your bid submission. If you have any questions regarding this addendum, please contact me via phone or email as listed below.

Sincerely,

Pete Patten
Purchasing Agent
608-267-3523
patten.peter@countyofdane.com

PRICE PROPOSAL – REVISED 6/18/2019

VENDOR NAME:

Pricing shall be inclusive of all labor, delivery costs and other expenses necessary to provide product in accordance with the specifications and terms and conditions of this bid document and your proposal.

**CTH P (CTH K to US 12) Town of Springfield, Sections 8, 17-19
Project No. 69**

Item #	Approx. Quantity		Item	Unit Price	Total Price
305.0100	72,735	SY	PULVERIZE AND RELAY	\$	\$
455.0605	2,909	GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$	\$
460.6223	12,548	TON	HMA PAVEMENT 3 MT 58-28 S, LOWER COURSE	\$	\$
460.6224	8,366	TON	HMA PAVEMENT 4 MT 58-28 S, UPPER COURSE	\$	\$
601.0557	854	LF	CONCRETE CURB & GUTTER 6" SLOPED 36-INCH, TYPE D	\$	\$
649.0150	720	LF	TEMPORARY MARKING LINE REMOVABLE TAPE, 4-INCH	\$	\$
TOTAL BID				\$	\$

PRICE PROPOSAL – REVISED 6/18/2019	
VENDOR NAME:	

Pricing shall be inclusive of all labor, delivery costs and other expenses necessary to provide product in accordance with the specifications and terms and conditions of this bid document and your proposal.

**CTH S (CTH P ‘Pine Bluff’ to Pioneer Road)
Towns of Cross Plains & Middleton
Project No. 69**

Item #	Approx. Quantity	Item	Unit Price	Total Price
305.0100	101,853	SY PULVERIZE AND RELAY	\$	\$
455.0605	4,074	GAL ASPHALTIC MATERIAL FOR TACK COAT	\$	\$
460.6223	17,750	TON HMA PAVEMENT 3 MT 58-28 S, LOWER COURSE	\$	\$
460.6224	11,833	TON HMA PAVEMENT 4 MT 58-28 S, UPPER COURSE	\$	\$
601.0407	806	LF CONCRETE CURB & GUTTER 18-INCH, TYPE D	\$	\$
601.0411	1,080	LF CONCRETE CURB & GUTTER 30-INCH, TYPE D	\$	\$
601.0557	854	LF CONCRETE CURB & GUTTER 6" SLOPED 36-INCH, TYPE D	\$	\$
602.0410	2,000	SF CONCRETE SIDEWALK 5-INCH		
602.0515	80	SF CURB RAMP DETECTABLE WARNING FIELD NATURAL PAT.		
620.0300	96	SF CONCRETE MEDIAN SLOPE NOSE TYPE 2		
649.0150	500	LF TEMPORARY MARKING LINE REMOVABLE TAPE, 4-INCH	\$	\$
TOTAL BID				\$