

## COUNTY OF DANE DEPARTMENT OF ADMINISTRATION PURCHASING DIVISION

City County Building 210 Martin Luther King Jr. Blvd. Room 425 Madison, WI 53703-3345

GREG BROCKMEYER Director of Administration CHARLES HICKLIN Controller

Date:May 2, 2019To:All ProposersSubject:Addendum #3 to Bid# 119055 – Tri-Axle and Patrol Truck Builds

There are 4 specifications in the Revised Specifications section on Addendum #2 that are off by 1 number/digit. This addendum corrects those numbers. Attached to this addendum (page 2) are the specification numbers that have been revised (in red). <u>Please print and use this</u> <u>document with your bid submission.</u>

Please acknowledge receipt of this addendum by checking the "Addendum #3" box in **Section 2 – Vendor Information** of your bid submission. If you have any questions regarding this addendum, please contact me via phone or email as listed below.

Sincerely,

Pete Patten Purchasing Agent 608-267-3523 patten.peter@countyofdane.com

## Section 3 – Bid Specifications – Submit with Bid

<b>REVISED SPECIFICATIONS – 5/2/2019</b>		Spec Compliance	
#	Item/Description	NO	YES
10	3/16" 201 Stainless Steel Rear Corner Posts with one cut-out for Recessed S/T/T Lights and one cut-out for strobe light. Exact locations to be determined at Pre-Build with Dane County.		
43	This specification has been deleted/removed.		
132	All Cross Tubes for Link Bolts are fully welded, fully greasable as well as the link arms and pivot bolts.		
133	This specification has been deleted/removed.		
223	A pair of Whelen VTX609A L.E.D. strobes mounted on the sides of the rear posts to be visible from the side. Must have guard to prevent "flash" in mirrors.		
224	Two (2) 2000 Lumen Clear L.E.D. Back-Up Lights rear mounted and wired Into Factory Back-Up Lights. Exact Locations to be determined at Pre-Build with Dane County - ST2000 Series Lights		
DC	Boards for the top of the boxes to be supplied and installed by Dane County.		