



COUNTY OF DANE
DEPARTMENT OF ADMINISTRATION
PURCHASING DIVISION
Room 425 City-County Building
210 Martin Luther King Jr. Blvd.
Madison, WI 53703-3345
608-266-4131
FAX 608-266-4425 TDD 608-266-4941

GREG BROCKMEYER
Interim Director of
Administration

CHARLES HICKLIN
Controller

DATE: July 28, 2017
TO: All Proposers BID #117075 – HMA & Cold Mix Pavement Projects
FROM: Pete Patten, Purchasing Agent
SUBJECT: ADDENDUM #4

This addendum contains revisions to specifications listed on Addendum #1. Please use and attach the revised bid specification and Price Proposals when submitting your proposal. The following individual projects affected by this addendum are:

- Specification
County Road TT (County Rd N to Ridge Rd) – Town of Sun Prairie
Project 69198-1700
- Specification
County Road T (Ridge Rd to Oak Park Rd) – Town of Medina
Project 69198-1700
- Specification
County Road T (Oak Park Rd to STH 19) – T of Medina & V Marshall
Project 69070-1600 CHIP Funded
- Price Proposal
County Road T (Oak Park Rd to STH 19) – T of Medina & V Marshall
Project 69070-1600 CHIP Funded

The entire Price Proposal section, including the most recent revisions, is attached to this addendum. Please use this attached price proposal when submitting your proposal.

- **No changes were made to the following projects, but please use the attached revised price proposal which contains all projects.**
 - CTH A
 - CTH DD
 - US 51

The bid submission deadline is not changed and will remain July 31, 2017 at 2:00 p.m.

Please acknowledge receipt of this addendum by noting “Addendum #4 Received” on the bottom of the Signature Affidavit when you submit your bid. If you have any questions regarding this addendum, please contact me at 608-267-3523.

Sincerely,

Pete Patten
Purchasing Agent

REVISED – 7/28/2017

County Road TT (County Rd N to Ridge Rd) – Town of Sun Prairie: Project 69198-1700
County Road T (Ridge Rd to Oak Park Rd) – Town of Medina: Project 69198-1700
County Road T (Oak Park Rd to STH 19) – T of Medina & V Marshall: Project 69070-1600
CHIP Funded

This project is broken into three sections which will be awarded as a single project.

- Section 1: CTH TT (CTH N to Ridge Road) & CTH T (Ridge Road to Oak Park Road)
- Section 2: CTH T (Oak Park Road to School Street)
- Section 3: CTH T (School Street to STH 19)

Dane County will be responsible for the following items: Replacing culverts in sections 1 & 2 and excavate and construct base for new curb and gutter and special waterway in section 3. Undercut in sections 2 & 3 will be done by County Forces, if required.

Contractor work on Sections 1 will include the following items: Milling Butt Joints & HMA Pavement. HMA pavement. HMA pavement will require a Carlson Curb to match existing section at various locations. Milling Butt Joints includes the following locations.

- West End of the Project
- 2 @ Bridge east of Kramer Ct
- 11 Intersections
- 16 Driveways

Contractor work on Section 2 will include the following items: Pulverized and Re-laid Pavement and HMA Pavement. In areas of curb and gutter and at butt joints hauling of excess material is the responsibility of the contractor and is incidental to the Pulverized Item. Contractor is responsible for providing squared off butt joints which is incidental to construction.

Contractor work on Section 3 will include the following items. Removing Asphaltic Surface (5-inches deep), Concrete Curb & Gutter, Concrete Sidewalk, Special Waterway and HMA Pavement. A detail drawing for the special waterway is available in Attachment A. Curb and gutter plans showing areas of new curb and cross-slopes throughout the curbed area is available in attachment B.

Note: Detectable warning fields will not be installed as shown on the plan between Stations 11+00 and 12+00. All curb, special waterway and sidewalk areas will be prepped by Dane County and ready at one time.

All roads will be open to traffic during construction. The contractor is responsible for traffic control signing and flagging during their operations. A minimum of two flaggers are required for all operations. The contractors traffic control is incidental to construction.

Proposed Pavement Structure

Pavement: Scratch: 4 LT 58-28 S, Contractor may option 5 LT 58-28 S
Lower: 4 LT 58-28 S
Upper: 4 LT 58-28 S

Approx. Length : CTH N to Ridge Road: 4.79 miles
Ridge Road to Oak Park Rd 2.34 Miles
Oak Park to School Street 0.70 miles
School Street to STH 19 0.34 miles

Width: CTH N to Ridge Road 30 feet
Ridge Road to Oak Park Rd 30 feet
Oak Park to School Street Varies 30' to 44'
School Street to STH 19 Varies 34' to 40'

Depth: CTH N to Ridge Road 1" Scratch, 2" Overlay

Ridge Road to Oak Park Rd	1" Scratch, 2" Overlay
Oak Park to School Street	3" Lower, 2" Upper
School Street to STH 19	3" Lower, 2" Upper

**Part 4 – Price Proposal
Submit With Bid**

Revised 7/28/17 – PRICE PROPOSAL – CTH A

**NAME OF
COMPANY:**

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

NO CHANGES MADE

**CTH A (State Highway 73 to East County Line) – Towns of Christiana and Albion
Project No. 69991-1700**

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	500 SY	REMOVING ASPHALT SURFACE MILLING	\$ _____	\$ _____
455.0605	2,650 GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$ _____	\$ _____
460.5224	5,900 TON	HMA PAVEMENT 4 LT 58-28 S, UPPER COURSE	\$ _____	\$ _____
649.0300	550 LF	TEMP PAVEMENT MARKING 4-INCH, REFLECTIVE TAPE	\$ _____	\$ _____
TOTAL BID				\$ _____

**Part 4 – Price Proposal
Submit With Bid**

Revised 7/28/17 – PRICE PROPOSAL – CTH DD

**NAME OF
COMPANY:**

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

NO CHANGES MADE

**CTH DD (South County Line to CTH D) Town Montrose
Project No. 69021-1700**

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	675 SY	REMOVING ASPHALT SURFACE MILLING	\$ _____	\$ _____
455.0605	1,100 GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$ _____	\$ _____
460.5224	2,350 TON	HMA PAVEMENT 4 LT 58-28 S, UPPER COURSE	\$ _____	\$ _____
649.0300	110 LF	TEMP PAVEMENT MARKING 4-INCH, REFLECTIVE TAPE	\$ _____	\$ _____
TOTAL BID				\$ _____

**Part 4 – Price Proposal
Submit With Bid**

REVISED 7/28/17 – PRICE PROPOSAL – County Road TT and T

**NAME OF
COMPANY:**

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

County Road TT (County Rd N to Ridge Rd) – Town of Sun Prairie: Project 69198-1700
County Road T (Ridge Rd to Oak Park Rd) – Town of Medina: Project 69198-1700
(NOTE: THIS PROJECT WILL BE AWARDED WITH PROJECT 69070-1600)

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	900 SY	REMOVING ASPHALTIC SURFACE, MILLING	\$ _____	\$ _____
455.0605	10,000 GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$ _____	\$ _____
460.6224	21,500 TON	HMA PAVEMENT 4 LT 58-28 S, UPPER CRSE.	\$ _____	\$ _____
649.0300	1,500 LF	TEMP PAVEMENT MARKING 4-INCH, REFLECTIVE TAPE	\$ _____	\$ _____
TOTAL BID				\$ _____

**Part 4 – Price Proposal
Submit With Bid**

REVISED 7/28/17 – PRICE PROPOSAL – County Road T

**NAME OF
COMPANY:**

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

**County Road T (Oak Park Rd to STH 19) – T of Medina & V Marshall:
Project 69070-1600 CHIP Funded
(NOTE: THIS PROJECT WILL BE AWARDED WITH PROJECT 69198-1700)**

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	6,900 SY	REMOVING ASPHALTIC SURFACE, MILLING	\$ _____	\$ _____
211.0120	1 LS	PREPARE FOUNDATION FOR ASPHALTIC PAVING (69198-1700)	\$ _____	\$ _____
305.0100	14,600 SY	PULVERIZE AND RELAY	\$ _____	\$ _____
455.0605	900 GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$ _____	\$ _____
460.6223	3,990 TON	HMA PAVEMENT 4 LT 58-28 S, LOWER CRSE.	\$ _____	\$ _____
460.6224	2,660 TON	HMA PAVEMENT 4 LT 58-28 S, UPPER CRSE.	\$ _____	\$ _____
601.0411	676 LF	CONCRETE CURB & GUTTER 30-INCH, TYPE D	\$ _____	\$ _____
602.0410	1,063 SF	CONCRETE SIDEWALK, 5-INCH	\$ _____	\$ _____
602.0420	378 SF	CONCRETE SIDEWALK, 7-INCH	\$ _____	\$ _____
602.0505	40 SF	CURB RAMP DETECTABLE WARNING FIELD, YELLOW	\$ _____	\$ _____
649.0300	80 LF	TEMP PAVEMENT MARKING 4-INCH, REFLECTIVE TAPE	\$ _____	\$ _____
SPV.0195.01	614 SF	SPECIAL WATERWAY PER SDD 3.01	\$ _____	\$ _____
TOTAL BID				\$ _____

**Part 4 – Price Proposal
Submit With Bid**

Revised 7/28/17 – PRICE PROPOSAL – US 51

**NAME OF
COMPANY:**

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

NO CHANGES MADE

US 51 (Pierstorff St to Hoepker Road) – City of Madison, Town of Burke

NOTE: The US 51 project is subject to Davis Bacon Wage Rate attached to this document. General Decision Number: WI170010 06/23/2017 WI10

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	23,270 SY	REMOVING ASPHALT SURFACE MILLING	\$ _____	\$ _____
455.0605	930 GAL	ASPHALTIC MATERIAL FOR TACK COAT	\$ _____	\$ _____
460.5224	2,700 TON	HMA PAVEMENT 4 LT 58-28 S, UPPER COURSE	\$ _____	\$ _____
TOTAL BID				\$ _____