COUNTY OF DANE

DEPARTMENT OF ADMINISTRATION

PURCHASING DIVISION

Room 425 City-County Building
210 Martin Luther King Jr. Blvd.
Madison, WI 53703-3345
608-266-4131
FAX 608-266-4425   TDD 608-266-4941

GREG BROCKMEYER
Interim Director of
Administration

CHARLES HICKLIN
Controller

DATE: August 14, 2017
TO: All Proposers BID #117079 – HMA Pavement for Wisconsin DOT Projects
FROM: Pete Patten, Purchasing Agent
SUBJECT: ADDENDUM #1

This addendum contains an additional project (Project #6) that will be incorporated into Dane County Bid# 117079. Please include and attach the Project #6 Bid Specification and Price Proposal sections contained within this addendum when submitting your proposal.

The bid submission deadline is not changed and will remain August 25, 2017 at 2:00 p.m.

Please acknowledge receipt of this addendum by noting "Addendum #1 Received" on the bottom of the Signature Affidavit when you submit your bid. If you have any questions regarding this addendum, please contact me at 608-267-3523.

Sincerely,

Pete Patten
Purchasing Agent

PROJECT #6
The two projects (6A and 6B) listed under Project #6 will be awarded together.

The projects in this bid are all WisDOT – Dane County Highway Department Maintenance Project. On behalf of WisDOT, Dane County Highway Department is advertising these maintenance milling and paving projects. **NOTE: All projects listed in this bid are subject to Davis Bacon Wage Rate attached to this document. General Decision Number: WI170010 06/23/2017 WI10**

PROJECT 6

6A) STH 73 (365 feet north of DNR Bike Trail), Village of Deerfield

Scope of Work:
This project is to mill a patch 200 feet long and 30 feet wide. Milling and paving depth is to be 2-inches. Pavement marking will be done by Dane County.

Work Hour Restrictions:
This project can be done during the non-peak hours of 8:30 a.m. to 3:30 p.m. Contractor must submit a traffic control plan for approval prior to the start of work. Entry of lane closures into WisDOT's LCS system is a requirement.

HMA Mix Design:
An asphalt mix design of 4 MT 58-28 S is specified for this project.

6B) STH 73 (90 feet south of Greenwood St), Village of Deerfield

Scope of Work:
This project is to mill a patch 250 feet long and 15 feet wide. Milling and paving depth is to be 2-inches. Pavement marking will be done by Dane County.

Work Hour Restrictions:
This project can be done during the non-peak hours of 8:30 a.m. to 3:30 p.m. Contractor must submit a traffic control plan for approval prior to the start of work. Entry of lane closures into WisDOT's LCS system is a requirement.

HMA Mix Design:
An asphalt mix design of 4 MT 58-28 S is specified for this project.

PROJECT #6 (6A) - PRICE PROPOSAL	
NAME OF COMPANY:	

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

PROJECT #6 (6A)
STH 73 (365 feet north of DNR Bike Trail), Village of Deerfield, Award with 6B

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	667 SY	REMOVING ASPHALT SURFACE MILLING	$ _____	$ _____
455.0605	26 GAL	ASPHALTIC MATERIAL FOR TACK COAT	$ _____	$ _____
460.6224	77 TON	HMA PAVEMENT 4 HT 58-28 H, UPPER CRSE	$ _____	$ _____
643.0100	1 LS	TRAFFIC CONTROL STH 73 PROJECT 6A	$ _____	$ _____
		TOTAL BID		$ _____

PROJECT #6 (6B) - PRICE PROPOSAL	
NAME OF COMPANY:	

For the price(s) listed below, our company hereby offers to provide the following item(s) in accordance with the specifications of this bid. Pricing must include delivery.

PROJECT #6 (6B)
STH 73 (90 feet south of Greenwood St), Village of Deerfield, Award with 6A

Item No.	Approx. Quantity	Item	Unit Bid	Net Bid
204.0120	417 SY	REMOVING ASPHALT SURFACE MILLING	$ _____	$ _____
455.0605	17 GAL	ASPHALTIC MATERIAL FOR TACK COAT	$ _____	$ _____
460.6224	48 TON	HMA PAVEMENT 4 HT 58-28 H, UPPER CRSE	$ _____	$ _____
643.0100	1 LS	TRAFFIC CONTROL STH 73 PROJECT 6B	$ _____	$ _____
		TOTAL BID		$ _____